
Design Basis Report

Campus Overview

Meridian Data Centre Campus Phase 1 supports 20MW IT load across 4 halls x 5MW.

Target PUE is 1.45.

Electrical Topology

UPS systems shall be N+1 per group.

Consultant

Designed by Apex Engineering.